BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Zone.

Tender Notification No:BBMP/YZ/EE(Ele)/TN/02/2016-17 Date: 2.07.2016

Operation and maintenance of Street Lights in Yelahanka Satellite town Ward , Ward No 4, Package Y4 of Yelahanka Zone.

Schedule-B

Sl No	Description	Unit	Qty	Rate Quoted by M/s Ganga Enterprises	
				Rate/ 12 Months in Rs	Rates in figures
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starter, Drawing of suitable capacity double insulated wire along with messenger wire in place of damaged LTUG cable of street lighting system and Painting of street light & park MS tubualar Poles and footing, Pole numbering ,switching ON/OFF of street lights at specified timing and Preparing data bank of street lights, TC wise & Circuit Wise Master register for each ward, removing of buntings Posters, threads, banners from the street light poles and carrying out routine maintenance, cleaning of perfex covers, pruning of trees around fittings periodically, furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below.				
	ii) Poles with 36/40 W fluorescent tube lights complete with luminaries, lamps, control gear and all accessories.	Each	38	45.00	Rupees Forty Five Only
	ii) Poles with 125 W HPMV lamps complete with luminaries, lamps, control gear and all accessories	Each	150	185.00	Rupees One Hundred and Eighty Five Only
	iiii) Poles with 250W HPSV lamps complete with luminaries, lamps, control gear and all accessories	Each	2685	491.00	Rupees Four Hundred and Ninty One Only
	v) Supply & Replacing of 400 watts HPSV light accessories complete with chokes,igniter, lamps, control gear,control ropes,internal mast cable,etc complete for High mast lighting system.	Each	132	505.00	Rupees Five Hundred and Five Only

For GANGA ENTERPRISES

Proprietor

	vi) Supply & Replacing of 400 watts HPMH light accessories complete with chokes,igniter, lamps, control gear,control ropes,internal mast cable,etc complete for High mast lighting system	Each	70	512.00	Rupees Five Hundred and Twelve Only
	vii) Poles with 24 W/ 48 W/ 60 W/ 72 W LED fittings complete with each Led, Control gear and all accessories including sealing lens perfex etc., complete	Each	50	1517.36	Rupees One Thousand Five Hundred Seventeen and Thirty Six Paise Only
2	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut-outs, wiring connector and M.S. Box with proper insulation etc., complete.	Each	83	1110.00	Rupees One Thousand One Hundred and Ten Only

For GANGA ENTERPRISES

I am Prepared to Take Up the above Work at The Rates Mentioned In the Schedule-B

Proprietor

CONTRACTOR

Executive Engineer (Ele)
Yelahanka Zone, BBMP